NPS Form 10-900-a (7-81)

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

Page 15

OMP NO. 1024-0018

EXP. 12/31/84

Continuation sheet

Item number 7

PART V: OLD VILLAGE HISTORIC DISTRICT

Boundary Justification (see Map 2)

The district includes the best preserved nineteenth and early twentieth century residential, commercial, ecclesiastical and institutional architecture remaining in Monroe on the south side of the River Raisin. Outside the district boundaries are modest nineteenth and early twentieth century residential areas of mostly undistinguished residences that have been unsympathetically altered by the addition of modern cladding materials, or the removal of original porches or decorative features.

Description

This Historic District is the largest in the Multiple Resource Study area and was the nucleus of much of Monroe's evolutionary development. The 1817 Old Village Plat and the adjoining pre-1850 plats constituting the Old Village Historic District encompass most of the concentrated urban development in Monroe up to about 1910, when intensive residential development began to shift to the large tracts of vacant land north of the River Raisin. It includes the city's business district and the major residential areas.

The core of the Old Village District is the commercial development lying between Cass and Macomb streets on Front Street. The evolution of the City can be traced outward from this commercial core. Surrounding the Central Business District are buildings oriented toward service and administrative uses such as the county courthouse, the city hall, the fire department and post office. From this point outward lie the city's major residential areas constructed before 1920. The building types and their spatial arrangement clearly indicate the City's periods of growth. Scattered throughout the district are churches and schools as well as two small pockets of concentrated industrial activity.

The commercial district on Front Street is predominantly of nineteenth century origin with some early twentieth century infill. Above the street level, many structures retain their original fenestration and cornices. Most of the buildings are brick, 3-story, flat-roofed, Italianate style buildings with arched fenestration, hood moulds, and corbelled brick cornices. Only a few wooden, false-fronted, store buildings survive intact, such as 119 East Front Street (photo #8). Among the more exceptional Italianate commercial blocks are 82 W. Front Street (photo #9) and the Augusta and Clark Block at 12-16 W. Front Street (photo #10).

Among the more notable twentieth century buildings are 123-125 E. Front Street (photo #15) with its foliated pediment and oriel windows; the Italian Renaissance style Monroe Bank & Trust Building (1910) (photo #16); the Georgian Revival style Detroit Edison Building (1928) (photo #17); and the Art Deco style Peoples Federal Savings & Loan Building (remodelled in 1930) (photo #18). The modest Monroe Theater (1938) (photo #20) is the only noteworthy example of the Art Moderne style.

Monroe has only two surviving old public buildings. The Monroe County Courthouse (photo #22), built in 1880, is an extraordinary example of Italianate design with its open loggia and asymmetrical towers. The only other surviving old public building is the former

NPS Form 10-900-a (7-81)

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

OME NO. 1024-0018

Continuation sheet

Item number

Page 16

Post Office (photo #24), a Georgian Revival style brick building constructed in 1911 and now used as the Monroe County Historical Museum.

Only one old public school remains in the district. The former Monroe High School (photo #26), built in 1928, is a fine, 3-story, flat-roofed, patterned-brick-and-terra-cotta-ornamented structure of Romanesque inspiration.

There are relatively few industrial buildings in Monroe. The most distinguished structure is the National Register listed Weis Manufacturing Company Complex which is outside the boundaries of the Old Village Historic District. Similar to it is the Floral City Furnace Company complex (photo #29) at 412 South Monroe Street. Built in the 1880s to replace an earlier foundry, it is a 2-story, brick structure with a symmetrical facade of regularly-spaced segmentally arched windows divided by brick piers and capped with a corbelled cornice.

The Amendt Milling Company complex on West Front Street (photos #30, 31) is one of the few surviving operations of its kind in Michigan. Its plant reflects various periods of growth from the 1900s to the 1960s. The old frame gambrel-roofed portion of the mill is justaposed with corbelled brick, gable-roofed blocks and a spelndid Beaux Arts style, hip-roofed office building to form a lively, picturesque composition.

All but one of the historic churches in Monroe is contained within the Old Village Historic District. Most of these are fairly similar, red brick, Victorian Gothic or Romanesque style structures with tall belfries. Most were built in the 1860s or 1870s. St. John's Catholic (photo #34), St. Michael's Catholic (photo #37), Trinity Lutheran (photo #35), First Presbyterian (photo #32), St. Paul's Methodist (photo #38), and First Baptist churches (photo #33) are typical of this type. Trinity Episcopal Church (photo #36) built in 1871 differs from its imposing contemporaries in that it is a ground-hugging, limestone structure of English Gothic design by Irish-immigrant architect John Addy.

The remainder of the buildings within the district are residences representing almost the complete spectrum of architectural styles popular in America from 1830 to 1930. Excellent examples of Federal (photos #39, 40), Greek Revival (photos #43, 44, 45), Gothic Revival (photo #41), Italianate (photos #46-50); Second Empire, (photos #52-54), Stick style (photo #55); Queen Anne (photo #56-58), Shingle style (photo #60), Colonial Revival (photo #63); Elizabethian Revival (photo #62), and Bungalow style houses (photos #64-66), are to be found, as well as decorated vernacular houses that fit less easily into standard stylistic categories.

NPS Form 10-900-a (7-81)

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

EXP. 12/31/01

Continuation sheet

Item number 7

Page 17

Significance

The Old Village Historic District is architecturally significant for its exceptional range and diversity of well-preserved structures representing virtually every stylistic building trend popular in Michigan between 1830 and 1930. It is historically significant as the nucleus of one of Michigan's oldest and most historic cities.

The Old Village Historic District traces its origins to 1817 when Joseph Loranger offered a portion of his land, south of the River Raisin, as a site for a new village. The offer was quickly accepted and the tract was platted into an orderly grid plan with a public square laid out just to the east of the main street, Monroe Street. The new village was named Monroe in honor of newly elected President James Monroe as was the newly created county it became the seat of. The population quickly shifted from Old Frenchtown on the northside of the river near the edge of the Great Marsh, to the more healthful environs of the new village.

Predictably for a river port, the commercial area developed along the river bank of Front Street. The courthouse was built on the public square, thereby, forever fixing the location of government activities. For decades there was no industry, except for milling operations and wood products processing, with the result that the rest of the village was devoted to residential land uses. For the balance of the nineteenth century, growth occurred within the limits of the Old Village Plat and the adjacent additions.

Architecturally, the Old Village Historic District contains buildings representing every period of the town's history from the 1820s into the 1920s. There are excellent examples of commercial, institutional and residential buildings illustrating the full range of architectural styles from Federal to Art Deco. Within each stylistic group there are high style examples as well as vernacular interpretations. Because of the town's single log development pattern, many of the streetscapes present a visual potpourri of randomly juxtaposed structures of widely differing architectural styles. The elegance of the buildings and the fine craftsmanship they exhibit is a testament to a century of continuouse prosperity. Since few architects are known to have been working in 19th century Monroe, the town's buildings are probably mostly the products of skilled builders adapting designs taken from pattern books or periodicals. Some buildings, especially institutional structures, were designed by architects imported from Toledo and Detroit. of the more notable structures in the district, exemplifying its architectural diversity, are described in the following partial inventory:

SAWYER RESIDENCE - 320 East Front Street (photo #46)

This impressive home stands on the site of one of the earliest buildings in Monroe. In 1785, Francis Navarre built a cabin on this site. Dr. Alfred I. Sawyer and his family lived there from his marriage in 1859 to 1870. It was then moved to make room for the present structure, which was completed in 1873. The Sawyer House is a two-story, brick, structure with single brackets beneath the cornice, vermiculated stone quoins, and other Italianate details. A cupola, twelve feet square, surmounts the hipped roof. There are fifteen large rooms, not counting the wide center hallways. Dr. Sawyer was one of the early proponents of homeopathy as the correct philosophy of medicine. He urged the Uni-

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

C. 1024-0013

Continuation sheet

Item number 7

Page 18

versity of Michigan to adopt this mode of medical practice and eventually his views prevailed, after ten years of fighting, when the University established the Department of Homeopathy and a homeopathic hospital. He was an American delegate of the International Homeopathic Congress in London in 1881 and was elected president of the National Institute of Homepathy in 1889. The house was given to the City of Monroe to be used as head-quarters for the Red Cross by Dr. Sawyer's daughter, Jennie, in 1938. The house continued to be used by the Red Cross, the Camp Fire Girls and the Monroe County Historical Society Museum until 1973. Presently, it is being restored by the City for use as a Women's Center. The house was listed individually on the National Register on November 23, 1977.

MANN HOUSE - 405 Washington Street (photo #41)

Easily the most unique home in Monroe, the Mann House was built in 1848 for Henry V. Mann. John Addey, an Irish trained architect, based his design on an Irish prototype. Henry V. Mann was a promoter of the Michigan Southern Railway, one of the first railroads in the State. Ten years later, in 1858, William Hunt Boyd purchased the house from Henry Mann. William Boyd, a direct descendent of the Earl of Richmond, was among the organizers of the Republican party and organized the First National Bank of Monroe. Gothic Revival in style, the pointed arch windows with their Gothic tracery in the upper portions are in sharp contrast to the overall cube forms of the stucco covered structure. Cast iron cresting was added sometime in the late nineteenth century.

OLIVER HOUSE - 204 East Second Street (photo #40)

The Oliver family were the earliest occupants of this building which was constructed of limestone transported from Kelly's Island in 1827. Rectangular blocks of limestone laid horizontally are outlined by think profiled mortar joints. Wooden dentils trim the eaves and gable end. The symmetrical 5-bay facade and the positioning of the windows portray a strong Federal style influence. The front porch and east and west additions were constructed in the 1930s.

JOHN GUTMANN RESIDENCE - 326 South Macomb Street (photo #56)

Built in 1890 by John Gutmann, and remodeled in 1928, this house retains the picturesque massing and the multiplicity of surface textures which was common to Queen Anne homes of the period. Narrow clapboard siding, fish-scale shingles, sunburst patterns, rosette detailed bargeboards, stained glass windows, ornamental brackets, beveled corners and a lively roofline are additional Queen Anne details.

JOSEPH WEIER HOUSE - 28 West First Street (photo #53).

The original owner of this fine building was Joseph Weier, a prominent local businessman. Built about 1880, this French Second Empire style structure, now housing the American Legion, is perhaps the best surviving example of this type of architecture in Monroe County. A centrally located tower on a symmetrical facade, together with the mansard roof, dormer windows, heavy vermiculated limestone lintels and paired consoles combine to create an atmosphere of distinguished formality. Details such as sawtooth dentils, small triangular dormer windows on the tower roof, and cast iron cresting add to the architectural enrichment and show the degree of aesthetic quality that marked Monroe's heritage in the late nineteenth century.

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

EXP . 12/31/84

For NPS use only
received
date entered

OMB NO. 1024-0018

Continuation sheet

Item number 7

Page 19

FREDERICK W MEIER RESIDENCE - 203 Cass Street (photo #55)

About 1880, Frederick Meier, a miller, built this brick residence combining elements of the Queen Anne and Eastlake styles. The multiple gabled roof, square corner tower, round corner turret, lattice-turned posts and spindles of the front porch are fine features. A variety of windows openings, bargeboards, stone beltcourses, brackets, consoles, cass iron cresting, and overall irregular plan combine to give this house its Queen Anne picturesqueness.

FLORAL CITY FURNACE COMPANY - 412 South Monroe Street (photo #29)

Now occupied by the Modern Packaging Corporation, this industrial building was once the factory of Floral City Furnace and Monroe Furnace and Found ry Company. Built about 1880, it stands on the site of a foundry built in 1835. This fine brick structure is characterized by its segmentally arched windows, an elaborate corbelled brick cornice, protruding brick piers between the window openings, arched entrance with cast iron gate, and a cast iron sign support on the roof's edge.

MONROE JUNIOR HIGH SCHOOL - 503 Washington Street (photo #26)

Originally constructed as a high school in 1928, it became Monroe Junior High School in 1975. Situated in the heart of the Old Village residential area, the detailing on the facade gives this Romanesque style structure architectural interest. The entry tower dominates the facade with its red terra-cotta and yellow and blue ceramic tile embellishment. The main entry is framed by a series of inset terra-cotta Romanesque arches enriched with intricate mouldings. Terra-cotta tiles in a variety of patterns ornament the shaft of the tower. Terra-cotta detailing is also found on the cornice and the other fenestration of the structure.

MONROE COUNTY COURTHOUSE - Loranger Square (photo #22)

After the previous courthouse burned, it was replaced by this fine structure completed in 1880. The new courthouse was the pride of the community and remains as a valuable reminder of Monroe's rich heritage. In spite of some rather undistinguished mid-twentieth century additions, the charm of the building has been little affected by the ravages of growth and change. It is a two-story, smooth-faced limestone structure with a pedimented, central 3-bay loggia, a modillion cornice and an elaborate, mansard-roofed corner tower. The unusual building is one of Michigan's most original essays in the Italian Renaissance Revival style.

FIRST PRESBYTERIAN CHURCH - 108 Washington Street (photo #32)

The church was first organized on January 13, 1820. This fine structure, located on Loranger Square is one of Monroe's oldest churches. Built in 1846 in the Greek Revival style, it was extensively remodeled with the addition of Victorian-Romanesque architectural features in 1863. Buttresses appear along exterior walls and windows have Gothic tracery within a Romanesque-rounded arch. The Boyd Chapel, attached to the west wall, was built in 1869. George Armstrong Custer and Elizabeth Bacon were married in this church.

National Register of Historic Places Inventory—Nomination Form

EXP. 12/01/34
For NPS use only
received
date entered

Continuation sheet

Item number 7

Page 20

FIRST BAPTIST CHURCH - 214 Washington Street (photo #33)

Originally built as the First Baptist Church of Monroe in 1870, the structure in recent years has been the home of the Monroe Assembly of God congregation. A small example of Gothic Revival ecclesiastical architecture, this church is often left unnoticed among the neighboring buildings. Buttresses, tall arches and a steeply pitched roof add to its style and verticality.

ST JOHN'S CATHOLIC CHURCH - 511 South Monroe Street (photo #34)

Although the congregation of St. John's was organized in 1871, the present church structure was not built until 1877. Constructed of brick, this interesting building combines Gothic Revival and Romanesque features. Buttresses run along the exterior walls and the windows, tower vents and main entry have rounded arches.

TRINITY LUTHERAN CHURCH - 323 Scott Street (photo #35)

Organized in 1844, the Trinity Lutheran congregation attended services in only one other building prior to the construction of the present church in 1893. This fine brick, late Victorian Gothic structure with its magnificent pointed arches and beautiful stained glass windows, it crowned by a tall spire atop an open corner belfry.

TRINITY EPISCOPAL CHURCH - 304 South Monroe Street (photo #36)

Organized in 1831, Trinity Episcopal's congregation held services in a Greek Revival style church building from 1832 until 1869. This fine Gothic Revival structure was dedicated in 1871. John Addy, the Irish trained architect who designed the Boyd House, assisted in the design of the church. This is the only church in Monroe to be constructed of rough faced limestone blocks rather than the red brick used to build the other churches in Monroe. The three tall pointed arch windows which face on South Monroe Street were furnished by Tiffany studios of New York.

ST. MICHAEL'S CATHOLIC CHURCH - 502 West Front Street (photo #37)

Long known as "The German Catholic Church," St. Michael's was organized in 1855. The congregation attended services in another building prior to the construction of this fine example of Victorian Gothic architecture in 1867-68 to the designs of Detroit architect Peter Dederichs. The steeple, not a part of the original construction, was added in 1883.

OLD POST OFFICE - 126 South Monroe Street (photo #24)

The office of John Knox Taylor, supervising architect of the United States Treasury Department, designed this building to serve as a U.S. Post Office in 1911. The building continued in use as a post office until 1969, when a new post office was built on West Front Street. The Monroe County Historical Museum occupied the structure in 1972 after the La-Z-Boy Foundation gave the Monroe County Historical Commission \$90,000 for its purchase. Architecturally, the arched windows with key stone motif across the front fa-

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

Continuation sheet

Item number 7

Page 21

OMB NO. 1024-5013

cade and the heavy cornice with large dentils and egg-and-dart molding are typical features of the Georgian Revival style. The projecting lanterns which flank the front entry are original. Occupancy by the museum is an important adaptive reuse of a prominent structure that stands as evidence of Monroe's architectural diversity.

MONROE THEATRE - 112 South Monroe Street (photo #20)

This modest structure is Monroe's best example of Art Moderne architecture. Built in 1938, the building retains much of its original detail. Red and green glazed panels cap the parapet while patterned brickwork suggests a cornice. A mottled effect is achieved through the use of multi-colored brick for the banded walls. Eight vertical strips of glazing and red and green tiling add to the vertical emphasis. On the street level, red panels have replaced those which were originally a shade of green similar to that on the cornice. The original vertical projecting sign between the glazed strips in the center of the upper facade has been removed. The dramatic effect of this facade was a deliberate attempt to lure people inside its doors.

OLD LOU'S SHOE REPAIR - 119 East Front Street (photo #8)

Originally constructed by a member of the Dansard family as a grocery store in the 1850s, the building has seen a variety of uses since that time. Most recently, and for many years previous, it was known as Lou's Shoe Repair. This structure stands as one of only two remaining wooden commercial structures in Monroe. Due to the extreme fire hazard wooden structures posed, brick buildings gradually replaced them. The front facade is comprised of a flush-boarded false front with four-over-four-double-hung sash with small window caps, and small brackets along the cornice. Behind this facade is a modest one and three-fourth-story, end-gable-roofed, clapboarded building.

PEOPLE'S FEDERAL SAVINGS AND LOAN COMPANY - 13 and 15 Washington Street (photo #18)

The main part of this structure was originally Italianate in style and was built about 1870 to serve as the Monroe City Hall. It served as the City Hall until 1930 when the City offices were moved to the Old Central School Building at 120 South Macomb Street (demolished). At that time the front facade was redesigned in the Art Deco style by architect Albert J. Hale for People's Federal Savings and Loan which utilized the building as their main offices until 1954. Milkins Jewelers and Towne Pharmacy now occupy the building. The facade is limestone with a marble base. Detailing consists of geometric patterned panels between projecting piers. The metal casement windows are also original. Many of the original bank fixtures and Art Deco interior decoration have survived in the jewelry store portion of the building.

COMMERCIAL BUILDING - 82 West Front Street (photo #9)

This brick store building is believed to have been built in 1877. The elaborate cornice with its large brackets and cut stone quoins and window hoods are interesting features of this Italianate style structure. The original storefronts are still intact complete with their cast iron Corinthian columns.

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

EXP. 12/31/84

For NPS use only
received
date entered

OMB NO. 1024-0016

Continuation sheet

Item number

Page 22

DETROIT EDISON BUILDING - 111 East First Street (photo #17)

In 1928, the Detroit Edison Company erected this residentially scaled, Neo-Georgian style office building on the northwest corner of Loranger Square. Built of brick with cut-stone detailing, the structure has a modillion cornice and delicate Federal doorway. Six-oversix and twelve-over-twelve, double-hung window sash with shutters add to the overall scale. Quarter-round windows appear on either side of the fireplace chimney in the gable end. A fine wooden clock tower with cupola dominates the roof line.

MONROE BANK AND TRUST BUILDING - 102 East Front Street (photo #16)

Constructed as the Dansard Bank about 1910, it replaced an earlier brick structure. Built of limestone and marble, the Beaux Arts style structure is dominated by the arcaded fenestration which occupies practically all of the wall area. A plain frieze and denticulated architrave mark the transition from the wall to the plain parapet. The corner entrance has a molded surround and projecting cap resting on consoles. The metal lanterns flanking the entrance and the wall-mounted, three-faced, box clock with ball finial are original features.

AUGUSTA AND CLARK COMMERCIAL BUILDING - 12-14 West Front Street (photo #10)

This example of French Second Empire style commercial architecture is one of the finest nineteenth century buildings in Monroe's business district. The mansard roof with its bracketed cornice and dentils and the tall narrow windows with hood molds and keystone motif dominate the facade. The mansard roof was originally embellished with three elaorately detailed circular dormer windows. The dormer windows were removed when the original slate shingles were replaced with asphalt shingles. The two storefronts have been altered.

National Register of Historic Places Inventory—Nomination Form

For NPS use only
received
date entered

Continuation sheet

Item number 7

Page 22a

NON-CONTRIBUTING BUILDINGS

All of the buildings within the Old Village Historic District are contributing structures except for the following:

East Front Street

- 227 Commercial Building (1947). A one-story brick veneer, plate glass front, non-descript commercial building with a pre-1900 two-story, wood frame, aluminum sided dwelling attached. (3M589)
- 303 Commercial Building (1947). A one-story, cement block, brick veneer, plate glass front, flat roofed, modern style, Commercial building. (3M154)

Harrison Street

212-16 Dwelling (1975). A 1-story, frame with brick veneer, modern-style, 3-family dwelling. (2M-335)

Island Street

102 Apartment Building (1964). A 2-story, brick, modern-style, 6-unit apartment house. (1M-223)

Murray Street

58 House (1951/1954). A two-story wood frame, face brick first floor, aluminum sided second floor, non-descript, dwelling and commercial building. (3M522)

O'Brien Street

711 Apartment Building (1965). A 2-story, brick veneer, pitched-roof, modern-style, 6-unit, apartment house. (1M-224)

Smith Street

212 K & K Supply Company (1949, 1960, 1970). A rambling, frame and concrete block, flat roofed, store building. (2M-40429)

South Macomb Street

- 28 Commercial Structure (1913). A one-story tile block, flat roofed, non-descript commercial building, with a two-story tile block, flat roofed warehouse, attached to the 1913 structure, built in 1945. (3M235)
- 119 Commercial Building (1965). A one-story face brick on cement block, flat roofed, modern style, commercial building, with a 1928, two-story, wood frame, hipped roof, vernacular four square style dwelling attached. (3M257)

National Register of Historic Places Inventory—Nomination Form

EXP . 12/31/8 1

For NPS use only
received
date entered

OMB NO. 1024 busto

Continuation sheet

Item number

Page 22b

- 313 House (1936). A 1-story, brick and asbestos sided, modern-style house. (3M-273)
- 315 House (1942). A 1-story, brick and perma-stone, modern-style house. (3M-274)

South Monroe Street

- 303 Gas Station (1952). 1 one-story, concrete block, porcelain tile and glazed brick, flat-roofed with parapet, gasoline and service station structure. (2M101 & 102)
- 311-315 Commercial Building (1913). A two-story, concrete block, face brick on tile front, flat-roofed, non-descript, commercial building. (2M103)
- 317 Commercial Building (1939). A two-story, concrete block, face brick on tile front, flat roofed, non-descript, commercial building. (2M104)
- 325 Commercial Building (1936). A one-story round cornered, wide round cornered sweeping overhang, concrete block, flat roofed, Art Deco-Moderne style, automotive commercial building. (2M105).
 - A $1\frac{1}{2}$ -story brick barn/carriage house with wood cupola, few alterations, situated on Parcel 2M105 behind the 1936 structure, is a contributing structure.
- 504 Gas Station (1950). A 1-story, concrete block, service station. (2M-192)
- 530-534 Office Building (1954, 1974). A 1-story, concrete block and brick veneer, flat-roofed, office building with an addition constructed in 1974. (2M-195).
- 602 Peoples Federal Savings and Loan (1953). A 1-story, brick veneer, flat-roofed, modern building. (2M-196)
- 629 Gas Station (1959). A one-story, cement block, brick veneer, plate glass floor to ceiling windows, shallow single pitched roof, modern style, gasoline station structure. (2M115)

Washington Street

612 House (1955). A one-story, cement block basement, brick veneer, gable-roofed, non-descript dwelling. (2M121)

West First Street

- 20 Gas Station (1965). A one-story, face brick, flat metal roofed, non-descript gasoline station structure. (2M238)
- 101 Commercial Building (1958). An attached, one-story, brick and plate glass, flat roofed, modern style, commercial building. (2M250)

West Second Street

226 Garage (1960). A one-story cement block, flat roofed, non-descript, garage. (2M402)

9. Major Biblio	ographica	al Refere	ence	S
Monroe: Monroe County Bulkley, John McClelland	/ Historical Cor d. History of M	mmission, 197 Monroe County	7. , Michi	gan: A Narrative Account of nterests. 2 Vols. Chicago:
10. Geograph	cal Data			
Acreage of nominated property	N/A			
Quadrangle name Monroe UMT References	 e-see U.S.G.S	. Mar		Quadrangle scale 1:24000
A	orthing	B Zon	e Easti	ng Northing
C		D		
Verbal boundary description Old Village Historic Dis				
		orth ROW line	of W.	Front Street and east ROW line (continued)
List all states and counties f	or properties over	lapping state or	county	boundaries
state N/A	code	county		code
state	code	county		code
11. Form Prep	ared By			
name/title Leslie J. Vollm	mert, Historic	Preservation	Coordin	ator
organization MI. History Div	vision, Dept. o	f State	date	January, 1982
street & number 208 N. Capit	col Avenue		telephon	e (517) 373-0510
city or town Lansing			state	Michigan 48918
12. State Hist	oric Pres	ervation	Offi	icer Certification
The evaluated significance of this	property within the	state is:		
national	state	X_ local		
As the designated State Historic 665), I hereby nominate this propaccording to the criteria and products that Historic Preservation Office	erty for inclusion in t edures set forth by the	he National Regis	ter and ce ervation a	
		1		3/2/63
titleDirector, Michigan His	story Division			date 3/3/82
I hereby certify that this pro	perty is included in	the National Regis	ater	
Keeper of the National Register	ature pro	se for le	slung	date
Attest:				date
Chief of Registration		HOLE PHILLS		

National Register of Historic Places Inventory—Nomination Form

orm

OMD NO. 1024-0013
EXP. 12/31/84
For NPS use only
received
date entered

Continuation sheet

Item number 10

Page 2

of Fishburn Alley; then north along said ROW line extended to the south bank of the River Raisin; then east along said bank to the line formed by the extension of the line of the west half of Lot 12 of the McClelland Plat; then south along side line to the south ROW line of East Front Street; then east along said ROW line to its intersection with the west ROW line of Navarre Street; then south along said ROW line to its intersection with the north ROW line of the alley between fifth and sixth streets, then west along said ROW line to the west ROW line of Wadsworth Street; then south along said ROW line to its intersection with the north ROW line of East Sixth Street; then west along said ROW line to its intersection with the west ROW line of LaPlaisance; then south along said ROW line to its intersection with the south lot line of W. Seventh Street; then west along said lot line extended to its intersection with the westROW line of Washington Street; then north along said ROW line extended to its intersection with the north ROW line of West Seventh Street; then west along said north ROW line to its intersection with the west lot line of the properties on the west side of South Monroe Street; then north along said west lot line extended to its intersection with the north ROW line of West Third Street; then west along said north ROW line extended to its intersection with the north ROW line of West Front Street; then west along said north ROW line to the point of beginning.

East Elm-North Macomb Street Historic District

Commencing at a point 140 feet east of the intersection of the E. ROW of North Macomb Street and the S. ROW of East Lorain Street; thence generally southerly and easterly along the rear lot lines of all property fronting the east side of North Macomb Street from the S. ROW of East Lorain Street to the N. ROW of East Hoble Avenue; thence westerly along the N. ROW of East Noble Avenue to the west line of the Lockwood and Little's Plat extended; thence southerly along the west line of the Lockwood and Little's Plat to the southwest corner of said Plat; thence generally easterly along the rear lot lines of all property presently fronting the north side of East Elm Avenue from the southwest corner of the Lockwood and Little's Plat to the E. ROW of Riverview Avenue; thence southerly along the E. ROW of Michigan Avenue extended to the north bank of the River Raisin; thence generally westerly along the north bank of the River Raisin to the southeast corner of the present Monroe Municipal Parking Lot; thence northerly along the east property line of the Municipal Parking Lot extended to the N. ROW of East Elm Avenue; thence westerly along the N. ROW of East Elm Avenue approximately 150 feet to the southeast corner of the present Downriver Federal Savings and Loan Association property (also described as City of Monroe Tax Parcel No. 6M 1307); thence generally northerly along the rear lot lines of all property presently frontingthe east side of North Monroe Street from the N. ROW of East Elm Avenue to the south line of the Noble Plat; thence westerly along the south line of the Noble Plat to the southwest corner of Lot 27 of the Noble Plat; thence northerly along the west property line of Lot 26 of the Noble Plat to the southeast corner of Lot 24 of the Noble Plat; thence westerly along the south property line of Lot 24 of the Noble Plat to the E. ROW of North Monroe Street; thence northerly along the E. ROW of North Monroe Street to a point 11.3 feet north of the N. ROW of East Noble Avenue; thence generally easterly along the rear lot lines of all property fronting the north side of East Noble Avenue from the E. ROW of North Monroe Street to a point 226 feet west of the W. ROW of North Macomb Street; thence North 24 30' E 153 feet; thence generally northerly along the rear lot lines of property presently fronting the West side of North Macomb Street from the N. ROW of East Noble Avenue to the S. ROW of East Lorain Street; thence easterly along the S. ROW of East Lorain Street to the Point of Beginning.

National Register of Historic Places Inventory—Nomination Form

CIT. NO. 1024-0018
EXP. 12/31/84
For NPS use only
received
date entered

Continuation sheet

Item number 10

Page 4

I. Property: Old Village Historic District

Acreage: aprox. 210 acres Quadrangle Name: Monroe Quadrangle Scale: 1:24000

UTM References:

- 17 300/360 4643/420 A В 17 301/820 4642/800 C 17 301/440 4642/260 D 17 301/250 4642/400 E 17 301/080 4642/060 F 17 300/800 4642/280 G 17 300/860 4642/360 H 17 300/700 4642/470 17 300/960 I 4642/830 J 17 300/300 4643/270
- II. Property: East Elm-North Macomb Street Historic District

Acreage: aprox. 50 acres Quadrangle Name: Monroe Quadrangle Scale: 1:24000

UTM References:

17 301/400 4643/620 В 17 301/620 4643/520 C 17 301/720 4643/750 301/820 D 17 4643/720 E 17 301/580 4643/180 F 17 301/850 4643/060 G 17 301/800 4642/950 17 301/260 4643/170

III. Property: St. Mary's Church Complex Historic District

Acreage: approx. 3 acres
Quadrangle Name: Monroe
Quadrangle Scale: 1:24000

UTM References:

A 17 301/240 4643/350

IV. Property: St. Mary's Academy Historic District

Acreage: approx. 69 acres Quadrangle Name: Monroe Quadrangle Scale: 1:24000

UTM References:

A 17 300/700 4644/200 B 17 301/120 4644/000 C 17 300/820 4643/450 D 17 300/480 4643/650

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

OMB NO. 1024-0018

EXP. 12/31/84

For NPS use only
received
date entered.

Continuation sheet

Item number

Page


Multiple Resource Area'...
Thematic Group

dnr-11

ta	teMichigan			
To	mination/Type of Review			Date/Signature
•	Old Village Historic District	Entered in the National Register	Keeper	5/6/82 Delwer By
		na orono.	Attest	***************************************
œ	East Elm-North Macomb Street Historic District	Entered in the National Register	Keeper	5/6/8 Delous By
		megister negister	Attest	
	St. Mary's Church Complex Historic District	Entered In the	Keeper	Tolor Delm B
		National Register	Attest	***************************************
	St. Mary's Academy Historic District	P OR IECTION	Keeper	Bur har Douge 5
	DOL) OWILL	W ODDECTION	Attest	determined light
	New York Central River Raisin Railroad Bridge		Keeper	Bur ha myd 6
		1	Attest	- Stellermen Blegebl
			Keeper	
			Attest	
			Keeper	
			Attest	
			Keeper	
			Attest	
			Keeper	
			Attest	
			Keeper	
			Attest	

EVALUATION / RETURN SHEET	820028
(City of Monroe MRA)	1 1
Property: Old Village Historic District	Working No. 3/23/82-8
State, County: MI Hanne	Fed. Reg. Date:
Federal Agency:	Date Due: 4/22/82 - 5/
	Action: ACCEPT_5/
resubmission	Entered in the RETURN_
nomination by person or local government	National Register REJECT
owner objection	photos
appeal	maps
Substantive Review:samplerequest _	appeal NR decision
Reviewer's comments:	2.61602
	Recom. / Criteria
	Reviewer
	Discipline
	Date
	see continuation shee
Nomination returned for: technical corrections substantive reasons 1. Name	
substantive reasons 1. Name	
substantive reasons	
substantive reasons 1. Name	
substantive reasons 1. Name 2. Location	
substantive reasons 1. Name 2. Location 3. Classification	
2. Location 3. Classification Cotogory Ownership Status Present Use Public Acquisition Accessible	
2. Location 3. Classification Colegory Ownership Status Present Use Public Acquisition Accessible 4. Owner of Property	
2. Location 3. Classification Cotogory Ownership Status Present Use Public Acquisition Accessible 4. Owner of Property 5. Location of Legal Description	
2. Location 3. Classification Cotogory Ownership Status Present Use Public Acquisition Accessible 4. Owner of Property 5. Location of Legal Description	discussed below
2. Location 3. Classification Cetegory Ownership Status Present Use Public Acquisition Accessible 4. Owner of Property 5. Location of Legal Description 6. Representation in Existing Surveys has this property been determined eligible? — ye	discussed below
2. Location 3. Classification Cetegory Ownership Status Present Use Public Acquisition Accessible 4. Owner of Property 5. Location of Legal Description 6. Representation in Existing Surveys has this property been determined eligible? — ye	discussed below
substantive reasons 1. Name 2. Location 3. Classification Cetegory Ownership Status Present Use Public Acquisition Accessible 4. Owner of Property 5. Location of Legal Description 6. Representation in Existing Surveys has this property been determined eligible?ye 7. Description Condition	discussed below
substantive reasons 1. Name 2. Location 3. Classification Cetegory Sumership Status Present Use Public Acquisition Accessible 4. Owner of Property 5. Location of Legal Description 6. Representation in Existing Surveys has this property been determined eligible?ye 7. Description Check one	discussed below
substantive reasons 1. Name 2. Location 3. Classification Cetegory Ownership Status Present Use Public Acquisition Accessible 4. Owner of Property 5. Location of Legal Description 6. Representation in Existing Surveys has this property been determined eligible?ye 7. Description Check one	discussed below
substantive reasons 1. Name 2. Location 3. Classification Cetogory Ownership Status Present Use Public Acquietien Accessible 4. Owner of Property 5. Location of Legal Description 6. Representation in Existing Surveys has this property been determined eligible?ye 7. Description Check one stellent deteriorated unaltered original site original site specified the present and original (N knewn) physical appearance summary paragraph	discussed below
2. Location 3. Classification Cetegory Ownership Status Present Use Public Acquisition Accessible 4. Owner of Property 5. Location of Legal Description 6. Representation in Existing Surveys has this property been determined eligible?ys 7. Description Check one Check one excellent deteriorated unaltered original site good ruins altered moved date Peccribe the present and original (M known) physical appearance summary paragraph completeness	discussed below
substantive reasons 1. Name 2. Location 3. Classification Cetegory Ownership Status Present Use Public Acquietien Accessible 4. Owner of Property 5. Location of Legal Description 6. Representation in Existing Surveys has this property been determined eligible?ye 7. Description Cendition Check one excellent deteriorated unaltered original site spood ruins altered moved date Fair unexposed Describe the present and original (N knewn) physical appearance summary paragraph	discussed below

Period Areas of Significance—Chook and justify below	
	TEXT TO THE PERSON OF THE PERS
Specific dates Builder/Architect	
Itatement of Significance (in one paragraph)	
summary paragraph	10000
completeness	
clarity	
applicable criteria	
justification of areas	
checked	
relating significance to the resource	
context	
relationship of integrity to significance	
justification of exception	
other	
and the state of t	
. Major Bibliographical References	
. Major Bibliographical helerences	
10. Geographical Data	
Rereage of nominated property	
UNIT References	
world ber	
volta bec.	
Ferbal boundary description and justification	
antid teri.	
motiva bed	Access to the second se
Perbal boundary description and justification	Series Constitute Cons
Perbal boundary description and justification	Server of the se
11. Form Prepared By	er Certification
11. Form Prepared By 12. State Historic Preservation Office	er Certification
11. Form Prepared By 12. State Historic Preservation Office	er Certification
Form Prepared By 12. State Historic Preservation Office The evaluated significance of this property within the state is:	er Certification
I 1. Form Prepared By I 2. State Historic Preservation Office the evaluated significance of this property within the state is:	er Certification
I 1. Form Prepared By I 2. State Historic Preservation Office the evaluated significance of this property within the state is:	er Certification
11. Form Prepared By 12. State Historic Preservation Office The evaluated significance of this property within the state is:	er Certification
11. Form Prepared By 12. State Historic Preservation Office The evaluated significance of this property within the state is:netionalstatelocal State Historic Preservation Officer signature date 3. Other	er Certification
11. Form Prepared By 12. State Historic Preservation Office The evaluated significance of this property within the state is:	er Certification
11. Form Prepared By 12. State Historic Preservation Office The evaluated significance of this property within the state is:netionalstatelocal State Historic Preservation Officer signature (Bitle dete 3. Other Maps Photographs	er Certification
11. Form Prepared By 12. State Historic Preservation Office The evaluated significance of this property within the state is:	er Certification
11. Form Prepared By 12. State Historic Preservation Office The evaluated significance of this property within the state is:	A Course of Steepe 1st Course of Cou
I 1. Form Prepared By I 2. State Historic Preservation Office the evaluated significance of this property within the state is:	A Course of Stape 1/2 Se English of Course in the Course of Cours
11. Form Prepared By 12. State Historic Preservation Office The evaluated significance of this property within the state is:netionalstatelocal Blate Historic Preservation Officer signature this Maps Maps Photographs	School States in Control State







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Looking west from Washington Street on the north side of E. Front Street, Old Village

Historic District

Photo #: 1 of 110





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Looking north on the east side of Washington


Street from Loranger Square; Old Village

Historic District

Photo #: 2 of 110

#1

32 F



my m

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe


120 E. First Street Monroe, MI. 48161

View: Looking west on the north side of West

Front Street; Old Village Historic District

Photo #: 3 of 110

#5







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Looking southwest at the corner of W. Front

and Monroe streets; Old Village Historic

District

Photo #: 4 of 110

R #5



5

5



TI

out St.

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161


View: Looking north at the west side of Monroe

Street from First Street; Old Village

Historic District

Photo #: 5 of 110

P 3





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe 120 E. First Street

Monroe, MI. 48161

View: Looking west on the north side of W. Front

Street from Monroe Street; Old Village

Historic District

Photo #: 6 of 110

45

15





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161


View: Looking southwest on the south side of W.

Front Street from Cass Avenue; Old Village

Historic District

Photo #: 7 of 110

#5







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 119 E. Front Street,

Old Village Historic District

Photo #: 8 of 110

#//





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development


City of Monroe

120 E. First Street Monroe, MI. 48161

View: 82 W. Front Street,

Old Village Historic District

Photo #: 9 of 110



10





Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 12-14 W. Front Street

Old Village Historic District

Photo #: 10 of 110



Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 29 E. Front Street

Old Village Historic District

Photo #: 11 of 110







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 27 E. Front Street;

Old Village Historic District

Photo #: 12 of 110









Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Looking south at the southeast corner of Monroe


and E. Front streets; Old Village Historic

District

Photo #: 13 of 110



R3 #4/A



A

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161


View: 23 E. Front Street;

Old Village Historic District

Photo #: 14 of 110



四年







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe


120 E. First Street Monroe, MI. 48161

View: The Reaper Building, 125 E. Front Street;

Old Village Historic District

Photo #: 15 of 110









Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161


View: Looking east at the Monroe Bank and Trust Build-

ing at the southeast corner of Washington and E.

Front Street; Old Village Historic District

Photo #: 16 of 110

#3 35FF







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe


120 E. First Street Monroe, MI. 48161

View: Looking northeast at the Detroit Edison Building

on Loranger Square; Old Village Historic District

Photo #: 17 of 110

7





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Looking east at 13-15 Washington Street;

Old Village Historic District

Photo #: 18 of 110



#3

34F



Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development


City of Monroe

120 E. First Street Monroe, MI. 48161

View: 14 South Monroe Street;

Old Village Historic District

Photo #: 19 of 110





Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Monroe Theater, 112 South Monroe Street;

Old Village Historic District

Photo #: 20 of 110

#5



N

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe


120 E. First Street Monroe, MI. 48161

View: Service station, 201 W. Front Street;

Old Village Historic District

Photo #: 21 of 110

19-91



N



Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Looking south at the Monroe County Courthouse,

Loranger Square; Old Village Historic District

Photo #: 22 of 110

#



Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Looking southwest at the Dorsch Memorial Library,

Loranger Square; Old Village Historic District

Photo #: 23 of 110

R 5





Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development


City of Monroe 120 E. First Street Monroe, MI. 48161

View: Looking west at the Monroe County Historical Mu-

seum (formerly Monroe Post Office), 126 South

Monroe Street; Old Village Historic District

Photo #: 24 of 110



S

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development


City of Monroe

120 E. First Street Monroe, MI. 48161

View: Former parochial school, 101 W. First Street;

Old Village Historic District

Photo #: 25 of 110





Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161


View: Monroe Junior High School (former Monroe High

School), 503 Washington Street; Old Village

Historic District

Photo #: 26 of 110

+3 267









Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe


120 E. First Street Monroe, MI. 48161

View: Detail of the entrance, Monroe Junior High School,

503 Washington Street; Old Village Historic

District

Photo #: 27 of 110







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: The Memorial to the Kentucky Militiamen slain in the River Raisin Massacre of 1813, Memorial Place,

600 block of S. Monroe Street; Old Village

Historic District

Photo #: 28 of 110

RI

#/3







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Looking southwest at the Modern Packaging Company

Plant (formerly Monroe Furnace and Foundry Com-

pany), 412 S. Monroe; Old Village Historic

District

Photo #: 29 of 110

#12



Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Looking southeast at the Amendt Milling Company

complex; 317 W. Front Street; Old Village

Historic District

Photo #: 30 of 110





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161


View: Looking northwest at the rear of the Amendt Mill-

ing Company complex, 317 W. Front Street; Old

Village Historic District

Photo #: 31 of 110





32



4

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161


View: Looking southwest at the First Presbyterian

Church, 108 Washington Street; Old Village

Historic District

Photo #: 32 of 110

#2





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe


120 E. First Street Monroe, MI. 48161

View: Monroe Assembly of God Church (originally First

Baptist Church), 214 Washington Square; 01d

Village Historic District

Photo #: 33 of 110



catholic

5 W

3

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe


120 E. First Street Monroe, MI. 48161

View: St. John's Catholic Church, 511 S. Monroe

Street; Old Village Historic District

Photo #: 34 of 110







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe


120 E. First Street Monroe, MI. 48161

View: Trinity Lutheran Church, 323 Scott Street;

Old Village Historic District

Photo #: 35 of 110

2 w







100

en Epise.

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development


City of Monroe

120 E. First Street Monroe, MI. 48161

View: Trinity Episcopal Church, 304 S. Monroe

Street; Old Village Historic District

Photo #: 36 of 110



m m



Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: St. Michael's Roman Catholic Church, 502 W.

Front Street; Old Village Historic District

Photo #: 37 of 110



30 Can Sundrudin

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe


120 E. First Street Monroe, MI. 48161

View: St. Paul's United Methodist Church, Monroe at E. Second Street; Old Village Historic District

Photo #: 38 of 110

D&







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Colonel Oliver Johnson House, 22 W. Second

Street; Old Village Historic District

Photo #: 39 of 110

R2 -19-51





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Oliver Family House, 204 W. Second Street;

Old Village Historic District

Photo #: 40 of 110







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161


View: Henry V. Mann House, 405 Washington Street;

Old Village Historic District

Photo #: 41 of 110

R1

23F





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 304 W. Front Street; Old Village

Historic District

Photo #: 42 of 110







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: David E. Noble House, 319 Washington

Street; Old Village Historic District

Photo #: 43 of 110







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 321 East Second Street;

Old Village Historic District

Photo #: 44 of 110

#4





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development


City of Monroe

120 E. First Street Monroe, MI. 48161

View: 30 Scott Street; Old Village

Historic District

Photo #: 45 of 110







sawyer Hoe

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Alfred I. Sawyer House, 320 E. Front Street;

Old Village Historic District

Photo #: 46 of 110

#3 00 F



Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 402 Washington Street;

Old Village Historic District

Photo #: 47 of 110





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 412 Scott Street;

Old Village Historic District

Photo #: 48 of 110





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 327 E. Second Street;

Old Village Historic District

Photo #: 49 of 110







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development


City of Monroe

120 E. First Street Monroe, MI. 48161

View: 328 E. Fourth Street;

Old Village Historic District

Photo #: 50 of 110





Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Detail of entrance to 720 O'Brien Street;

Old Village Historic District

Photo #: 51 of 110







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe


120 E. First Street Monroe, MI. 48161

View: Looking west at 303 and 309 (foreground)

E. Fifth Street; Old Village Historic District

Photo #: 52 of 110

+1







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Joseph Weier House, 23 W. First Street;

Old Village Historic District

Photo #: 53 of 110







616 Front St



Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 616 W. Front Street;


Old Village Historic District

Photo #: 54 of 110

4







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Frederick Meier House, 203 Cass Street;

Old Village Historic District

Photo #: 55 of 110







Gutman L

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: John Guttman House, 326 S. Macomb Street;

Old Village Historic District

Photo #: 56 of 110

#5



Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Detail of the front porch, 211 S. Macomb

Street; Old Village Historic District

Photo #: 57 of 110







2/

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe


120 E. First Street Monroe, MI. 48161

View: 703 S. Monroe Street;

Old Village Historic District

Photo #: 58 of 110

R4 32



259 g. nouse



Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 228 South Monroe Street;

228 South Monroe Street; Old Village Historic District

Photo #: 59 of 110

RI







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 608 Scott Street;

Old Village Historic District

Photo #: 60 of 110



Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street

Monroe, MI. 48161

View: 208 E. First Street;

Old Village Historic District

Photo #: 61 of 110









Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 322 E. Second Street;

Old Village Historic District

Photo #: 62 of 110

#4



Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: 322 East Fifth Street;

Old Village Historic District

Photo #: 63 of 110

Eng.







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street

Monroe, MI. 48161


View: 615 S. Washington

Old Village Historic District

Photo #: 64 of 110

#3

27A







Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development


City of Monroe

120 E. First Street Monroe, MI. 48161

View: 125 E. Seventh Street;

Old Village Historic District

Photo #: 65 of 110



637 weghington

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development


City of Monroe

120 E. First Street Monroe, MI. 48161

637 Washington Street; View:

Old Village Historic District

Photo #: 66 of 110







211 S. Macards w/ Fancy porch

Monroe Multiple Resource Nomination Monroe, Monroe County, Michigan

Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161

View: Looking north on the east side of S. Macomb

Street from E. Third Street; Old Village

Historic District

Photo #: 67 of 110

& coul



Photographer: Unknown

Date: 1981

Negative: Dept. of Community Development

City of Monroe

120 E. First Street Monroe, MI. 48161


View: Looking east in the 100 block of E. Seventh

Street; Old Village Historic District

Photo #: 68 of 110







Please refer to the map in the Multiple Property Cover Sheet for this property

Multiple Property Cover Sheet Reference Number: